## LEGEND:

| | |
|---|---|
| G | GAS LINE |
| SS | SANITARY SEWER |
| SD | STORM DRAIN LINE |
| JT | JOINT TRENCH |

GOLDENROD DRIVE

ARROWHEAD AVENUE

TREEFLOWER DRIVE

(8'x12' METAL SHED) (TO BE REMOVED)
(P.G.&E. GAS LINE)
(CITY 8" SEWER)
(CITY 18" STORM)
(8'x10' WALK-IN COOLER) (TO BE MOVED TO NEW KITCHEN)
(10'x12' WOODED STORAGE SHEDS) (TO BE REMOVED)
(FIRE HYDRANT)
(FIRE PI VALVES)
(MAIN GAS VALVE/METER)
(EX SUMP PUMP)
(MAIN ELECTRIC PANEL)
(ELECTRICAL TRANSFORMER)
(WATER TANK 80gal)
(WATER RISER 8"DIA/2'H)
(6' REDWOOD FENCE)
(4' WIRE FENCE) (TO BE REMOVED)
(CONCRETE WALL)
P.G.&E. EASEMENT (BK 1404 BK 30)
(P.G.&E. TOWER)
(CURB)
SEE ENLARGEMENT OF THIS AREA ON SHEET 2
FACE OF CURB
(COOLER)
(SHED)
(GRASS)
(CONCRETE)
(ASPHALT)
(FIRE SERVICE 4"DIA/2'H)
(GATE)
10' P.G.&E. GAS ESMT (85-052383)
(LAWN AREA)
(EX TREE) (TYP)
(GREASE TRAP)
(ASSEMBLY HALL)
(TEMPLE)
ELECTRIC SUB-PANEL
(100 AMP) (SUB-PANELS)
(LAWN AREA)
(WALL)
10' STORM ESMT (84-225437)
10' SEWER ESMT (84-225436)
SIDEWALK FACE OF CURB
SEE ENLARGEMENT OF THIS AREA ~ SHEET T-2
(6' CL FENCE AT WALL)
(4'CONC WALL)
(GATE)
10' SEWER ESMT (84-225433)
(TRAILER)
(FOOT WASH WATER TAP'S)
(200 AMP SUB-PANEL)
(EX SUMP PUMP)
(CONSTRUCTION OFFICE TRAILER-12'x 63') TO BE REMOVED
(EX BACK-FLOW)
(EX WATER METER)
(EP)
(4' WIRE FENCE)
6' REDWOOD FENCE
(OVERHEAD WIRE)
10' STORM ESMT (84-225434)
P.G.&E. EASEMENT (REEL 452 IM 863)
15' P.G.&E. GAS ESMT's (BK4216 PG 261)
P.G.&E. EASEMENT (BK 1404 BK30)
(FENCE)
20LF FENCE TO BE REMOVED
EX 10' SAN SEWER EASEMENT
EX 15' STORM DRAIN EASEMENT
EX PG&E TOWERLINE & GAS PIPE LINE EASEMENT
1"=40'
40 20 0 40 80
SCALE IN FEET

SEE SHEET 2

T-1

# TOPOGRAPHIC SURVEY

## HINDU COMMUNITY AND CULTURAL CENTER

1232 ARROWHEAD AVENUE

CITY OF LIVERMORE ALAMEDA COUNTY CALIFORNIA

JAMES E. DIGGINS R.C.E. 27818
RENEWAL DATE: 03/31/10

| # | REVISIONS | DATE |
|---|---|---|
| | | |

DeBolt Civil Engineering
811 San Ramon Valley Boulevard
Danville, California 94526
Tel: 925/837-3780
Fax: 925/837-4378

P:\P06309\T1-T2-T5.dwg 8/17/09 8:41

Date: 8/14/09
Scale: 1" = 40'
By: JED / kl
Job No.: 06309